RED THREAD® HP 16 Bar Piping System

SPECIFICATION GUIDE

SECTION 1 - Scope

This section covers the use of fiberglass reinforced plastic (FRP) pipe for mild chemical and water services up to 210°F and 450 psig steady pressure.

The piping system shall be furnished and installed complete with all fittings, joining materials, supports, specials, and other necessary appurtenances.

SECTION 2 - General Conditions

2.01 <u>Coordination</u> - Material furnished and work performed under this section shall be coordinated with related work and equipment specified under other sections.

Valves	Section	
Supports	Section	
Equipment	Section	

2.02 Governing Standards - Except as modified or supplemented herein, all materials and construction methods shall comply with the applicable provisions of the following specifications and be tested using the following standards:

Standard Specifications

ASTM D2996	Standard Specification for Filament-Wound "Fiberglass" (Glass-Fiber-Reinforced-Ther- mosetting Resin) Pipe	
ASTM 4024	Standard Specification for Reinforced Thermosetting Resin (RTR) Flanges	
ASTM D5685	Standard Specification for "Fiberglass" (Glass-Fiber-Reinforced-Thermosetting-Resin) Pressure Pipe Fittings	

Standard Test Methods

ASTM D2992	Standard Practice for Obtaining Hydrostatic or Pressure Design Basis for "Fiberglass" (Glass-Fiber-Reinforced-Thermosetting Resin) Pipe and Fittings
ASTM D2925	Standard Practice for Measuring Beam Deflection of Reinforced Thermosetting Plastic Pipe Under Full Bore Flow
ASTM D1599	Standard Test Method for Short-Time Hydraulic Failure Pressure of Plastic Pipe, Tubing and Fittings
ASTM D2105	Standard Test Method for Longitudinal Tensile Properties of "Fiberglass" (Glass-Fiber-Reinforced-Thermosetting Resin) Pipe and Tube
ASTM D2412	Standard Test Method for Determination of External Loading Characteristics of Plastic Pipe by Parallel-Plate Loading

2.03 Operating Conditions - In addition to the above listed minimum design requirements, the system shall meet the following minimum operating conditions:

a. Operating Pressure	
b. Operating Temperature	
c. Fluid Conveyed	
d. Test Pressure	

2.04 <u>Quality Assurance</u> - Pipe manufacturer's quality program shall be in compliance with ISO 9001 and/or API Q1.

2.05 Delivery, Storage, and Handling - Pipe and fittings shall be protected from damage due to impact and point loading. Pipe shall be properly supported to avoid damage due to flexural strains. The contractor shall not allow dirt, debris, or other extraneous materials to get into pipe and fittings. All factory machined areas shall be protected from sunlight until installed.

2.06 Acceptable Manufacturers - NOV Fiber Glass Systems, 501-568-4010, or approved equal.

SECTION 3 - Materials and Construction

3.01 2"-24" Pipe - The pipe shall be manufactured by the filament winding process using an amine cured epoxy thermosetting resin to impregnate strands of continuous glass filaments, which are wound around a mandrel at a 54³/4° winding angle under controlled tension. Pipe shall be heat cured and the cure shall be confirmed using a Differential Scanning Calorimeter.

Pipe shall be supplied with a matching tapered bell and a matching tapered spigot.

Pipe shall have a minimum continuous steady pressure rating of 225 psig at 210°F in accordance with ASTM D2992 Procedure A.

All pipe shall be 100% hydrotested at the factory before shipment at a minimum pressure of 300 psig.

3.02 Flanges and Fittings - All fittings shall be manufactured using the same type materials as the pipe. Fittings may be manufactured either by compression molding, sprayup/contact molding, or filament winding methods.



Fittings shall be adhesive bonded matched tapered bell and spigot, threaded or grooved adapters, or flanged. Fittings shall be certified to ASTM D5685.

Flanges shall have ANSI B16.5 Class 150 bolt hole patterns.

- **3.03** Adhesive Adhesive shall be manufacturer's standard for the piping system specified.
- **3.04** Gaskets Gaskets shall be ¹/8" thick, 60-70 durometer full-face type suitable for the service shown on the drawings and as recommended in the manufacturer's standard installation procedures.
- **3.05** Bolts, Nuts, and Washers ASTM A307, Grade B, hex head bolts shall be supplied. SAE washers shall be supplied on all nuts and bolts.
- **3.06** Acceptable Products RED THREAD II as manufactured by NOV Fiber Glass Systems, or approved equal.

SECTION 4 - Installation and Testing

4.01 Training and Certification - All joints installed or constructed in the field shall be assembled by employees of the contractor who have been trained and certified to the Bonding Procedure Specification (BPS) provided by the pipe manufacturer. The BPS shall meet or exceed the requirements of ASME B31.3, Section A328.2.1. The pipe manufacturer or their authorized representative shall train the contractor's employees in the proper joining and assembly procedures required for the project, including hands-on participation by the contractor's employees in accordance with the BPS. Each bonder shall fabricate one pipe-to-pipe and one pipe-to-fitting joint for qualification testing. The pipe size and test pressure used in the qualification assembly shall meet or exceed the minimum requirements of ASME B31.3. Only bonders who have successfully completed the qualification pressure test shall bond pipe and fittings.

4.02 <u>Pipe Installation</u> - Pipe shall be installed as specified and indicated on the drawings. The piping system shall be installed in accordance with the manufacturer's current published installation procedures.

Each pressure containing joint shall be clearly marked to identify the bonder in accordance with ASME B31.3, Section A328.5.1.

4.03 Testing - Hydrostatic testing should be performed to evaluate the structural integrity of a new piping system installation. Test pressures of 1.5 times the design pressure but not exceeding 1.2 times the static pressure rating of the lowest rated fiberglass component in the piping system are recommended. Contact the company if test pressures exceed 450 psig before testing. The hydro test pressure should be repeated up to ten times to provide a high degree of confidence in the piping system. The final pressurization cycle should be allowed to stabilize for 15-30 minutes, then inspected for leaks. Do not attempt to repair leaks while system is pressurized. The hydro test should be repeated after any re-work is performed.

When hydro testing, open vents to prevent entrapment of air in the lines as the system is slowly filled with water. Then close the vents and slowly pressurize to the test pressure. Upon completion of hydrotest, relieve the pressure on the system slowly, open vents and any drains to allow for complete drainage of the system.

Piping systems with design temperatures above 150°F should be tested at 1.2 times the static pressure rating of the lowest rated fiberglass component in the system.

National Oilwell Varco has produced this brochure for general information only, and it is not intended for design purposes. Although every effort has been made to maintain the accuracy and reliability of its contents, National Oilwell Varco in no way assumes responsibility for liability for any loss, damage or injury resulting from the use of information and data herein nor is any warranty expressed or implied. Always cross-reference the bulletin date with the most current version listed at the web site noted in this literature.

North America 17115 San Pedro Ave. Suite 200 San Antonio, Texas 78232 USA Phone: 210 477 7500 South America Avenida Fernando Simoes Recife, Brazil 51020-390 Phone: 55 31 3501 0023 Europe PO. Box 6, 4190 CA Geldermalsen, The Netherlands Phone: 31 345 587 587 <u>Asia Pacific</u> No. 7A, Tuas Avenue 3 Jurong, Singapore 639407 Phone: 65 6861 6118 <u>Middle East</u> P.O. Box 17324 Dubai, UAE Phone: 971 4881 35665



